



Status of RTI/Eastman Warm Gas Clean-up Technology and Commercialization Plans

Raghubir Gupta, Brian Turk, and Markus Lesemann
RTI International

Jerry Schlather and David Denton
Eastman Chemical Company


Gasification Technologies Conference
October 8, 2008

Syngas Cleaning Technology Platform




Operating Temperatures > 250 °C (482°F)


Process Integration – Modular Approach



Transport Desulfurization Reactor System



Commercial FCC Reactor
Source: KBR



RTI – Eastman High Temperature Desulfurization Process

Desulfurization Sorbent Characteristics

- ZnO supported on zinc aluminate
 - High attrition resistance (mechanical stability)
 - Inert support (chemical stability)
- Unique highly dispersed ZnO nanostructures with grain size <50 nm
 - High reactivity (short residence time in the reactor)
- Produced on commercial scale by major catalyst manufacturer
- Covered by US/International patents
- Won 2004 R&D 100 Award



Installed Pilot Plant Systems

Eastman's Kingsport, TN, Coal Gasification Facility

Direct Sulfur
Recovery
Process (DSRP)



High Temperature
Desulfurization
Process (HTDP)

Multi-contaminant
Control Test System
(MCC)


Eastman Gasification Plant

The image shows the Eastman Gasification Plant, a large industrial facility with various structures, pipes, and towers. A yellow oval highlights a specific section of the plant, which is identified as the RTI Field Test Systems. The plant is set against a blue sky with some clouds, and there are cherry blossom branches in the foreground on the right side. A sign in the foreground reads "ROUTE 28-29".

**RTI Field Test
Systems**

EASTMAN

Typical Sulfur Concentrations in Effluent Syngas



Dirty syngas composition: 7,771 ppmv H₂S
440 ppmv COS

Desulfurization Pilot Plant Summary of Parametric Testing

More than 3,000 hours of syngas operation


Pressure, psig	300	450	600
Inlet Concentration, S ppmv	8,661	7,023	8,436
Effluent Conc. S ppmv	5.9	10.7	5.7
Range	0.4 – 9.3	2.4-20.6	3.3-18.1
S Absorbed, lbs/hr	4.1	4.4	5.0
S Removal, %	99.93	99.82	99.90

- Average attrition rate: 31 lbs/MM lbs of sorbent circulated

Typical attrition rate for FCC catalysts is 50-100 lbs/MM lbs of catalyst circulated.

All data are averages over multiple hours of operation

Desulfurization Process Reliability



On-Stream Factor

Pre-improvements ~60%

Post-improvements >80%

Direct Sulfur Recovery Process


Reaction chemistry:



Temperature: 500-600°C


Pressure: 300-600 psig

Reactor design: Fixed bed



DSRP Operations

- Integrated operation
 - Effluent from regenerator of transport desulfurization system
 - Real coal-derived syngas
- 99.8% SO₂ conversion
- Produced liquid sulfur product




Multicontaminant Control Removal

- Removal of contaminants other than sulfur from syngas under high-pressure, high-temperature conditions
- Target contaminants: Hg, As, Cd, Se, HCl, Ammonia, HCN
- Test program
 - Extensive sorbent screening at RTI
 - Capacity tests on selected sorbents
 - Evaluation of potential process integration issues
 - Effect of S on sorbent effectiveness for other contaminants
 - Multicontaminant effects
 - Field demonstration of most promising sorbents with coal-derived syngas at Eastman



Ammonia and trace metal skid for testing at Eastman

Multi-contaminant Control Test System (MCC)




Test Conditions with Coal-derived Syngas

Temperature: 200°C
 Pressure: 850 psig
 Flow: 500 scfh
 Time: 525 hours

Arsenic Removal during Field Test


- As loading at bed inlet was 1 wt%
 - 3 wt% capacity demonstrated with simulated syngas
- No As breakthrough observed



Demonstrated effective As removal from coal-derived syngas at high temperatures and pressures

Mercury Removal during Field Test

- High Hg concentrations detected at syngas inlet to As sorbent bed
- No Hg breakthrough observed
- Hg concentrations in Hg sorbent bed were below detection limits



Demonstrated effective multi-contaminant removal of Hg and As from coal-derived syngas at high temperatures and pressures

Ammonia/HCN Removal

- Acidic Adsorbent
 - Regenerated by temperature swing
- Multiple fixed-beds for continuous NH₃/HCN removal
- Results with coal-derived syngas
 - NH₃
 - Inlet NH₃: 440 -500 ppmv
 - Outlet NH₃: 6-20 ppmv
 - HCN
 - Inlet HCN: ~50 ppmv
 - Outlet HCN: ~1 ppmv

Demonstrated effective NH₃ and HCN removal from coal-derived syngas at high temperatures and pressures.



Field Testing Summary

Field test demonstrated clean-up performance with real coal-derived syngas at high temperatures and pressures

- Phase I: Desulfurization technologies demonstrated
 - Transport desulfurization system
 - Desulfurization performance, process control, stability and reliability
 - Desulfurization sorbent
 - Mechanical strength, chemical activity, long-term stability
 - Direct Sulfur Recovery Process
 - Fully integrated operation of HTDP and DSRP
- Phase II: Modular fixed-bed cleanup for As, Hg, NH₃/HCN
 - Regenerable NH₃/HCN adsorbent
 - As and Hg sorbents

High-Temperature CO₂ Removal

- $\text{Li}_4\text{SiO}_4 + \text{CO}_2 \rightarrow \text{Li}_2\text{CO}_3 + \text{Li}_2\text{SiO}_3$
- $\text{CO} + \text{H}_2\text{O} \rightarrow \text{CO}_2 + \text{H}_2$
- Temperature: 250 to 500°C, Pressure: 300-600 psig



CO₂ removal from syngas at high temperatures and pressures with lithium silicate sorbent in pre-pilot phase

Techno-economic Evaluation – Comparison Basis

Project technical analysis performed by Nexant

Common Elements

- Illinois No. 6 Coal (2006 DOE, preliminary)
- U.S. Midwest site
- Nominal 600 MW capacity
- GE Gasification – Radiant Cooling
- Conventional cryogenic ASU without integration to GT
- GE 7FB based power train

Different Elements

Base Case

- Gas Quench & Scrubbing
- Low Temp. Gas Cooling
- Selexol™ AGR
- Claus sulfur recovery with SCOT tail gas treating
- Ambient Temperature mercury removal

Warm Gas Clean-up

- Convective Cooler
- Warm Gas Desulfurization Process (WGDS)
- High Temperature Mercury Removal Process
- SCR (no LT cooling to remove NH₃)

Results from Nexant's analysis have been confirmed by independent study by Noblis 20

Performance Comparisons

	IGCC Base Case	IGCC with WGPU	Improve ment
<u>Imports or Feeds</u>			
Coal Feed, STPD (AR)	5,467	5,467	
95% Oxygen, STPD	4,665	4,895	-4.9%
99% N2, STPD	7,024	3,959	43.6%
Make Up Water, GPM	5,646	4,288	24.1%
<u>Exports or Products</u>			
Electric Power, MW	585	641	9.6%
Sulfur, STPD	137	137	
Slag & Ash, STPD (dry)	562	562	
Waste Water, GPM	2,798	1,085	61.2%
<u>Thermal Efficiency</u>			
HHV %	37.6	41.2	9.6%
LHV %	39.3	43.1	9.7%

Efficiency Improved 3.6 points HHV

Capital Cost Summary

Capital Cost, \$MM	IGCC Base Case	IGCC with WGPU
Coal Handling	17.8	17.8
Gasification Block	227.3	227.3
Air Separation	80.5	83.2
COS Hydrolysis and LT Cooling	37.2	0.0
ARG and Sulfur Recovery	185.1	168.4
Plant Air & N ₂ Compression	23.8	15.0
Gas Turbine Generators	146.4	145.0
HRSG & BFW Systems	49.0	55.6
Steam Turbine Generator	49.2	56.1
Balance of Plant	196.4	187.2
Home Office Cost	101.3	95.5
Total	1,114.0	1,051.1
Net Power Export, MWe	585.0	641.0
Cost per Unit Output \$/KWe	1,904.0	1,640.0

\$264/KW CAPEX IMPROVEMENT

Summary of Techno-Economic Evaluation for Power Applications

- Comparison of Eastman/RTI Warm Gas Clean-Up technologies with conventional syngas clean-up technologies performed by Nexant
 - 600 MW case study
 - Increase efficiency by 3.6 points HHV
 - Dispatch 56 MWe more power
 - Reduce CAPEX by \$264/KW
 - Reduce COE by 0.69 ¢/kwh
- Independent analysis performed by Noblis under NETL funding produced similar results

Conclusions

- Eastman/RTI Pilot Plant Testing:
 - Demonstrated technology readiness
 - Achieved desulfurization performance targets with real syngas
 - Additional fixed bed syngas cleaning options slipstream tested with real coal-derived syngas (HCl, NH₃, As, Hg, and Se)
- Technology package ready for power applications
- R&D efforts underway for chemicals/fuels application
- High-temperature CO₂ removal is being integrated

Commercialization

- Scale-up to 20-50 MW demonstration plant envisioned
- Discussions underway with potential test sites
- Engineering design package assembled
- Comprehensive technology package ready for power applications

Acknowledgments

- Financial Support from DOE/NETL
 - Contract No. DE-AC26-99FT40675
 - Cooperative Agreement No. DE-AC26-05NT42459
- Technical Guidance
 - Gary Stiegel (DOE/NETL)
 - Daniel Cicero (DOE/NETL)
 - Suresh Jain (DOE/NETL)
 - Jenny Tennant (DOE/NETL)
 - Gopala Krishnan (SRI International)
 - Gunnar Henningsen
 - Ted Knowlton (PSRI)